Footing Type				Results													
Detail	Qty	Key	Length	Width	Pier Ln	Pier Wd	Pier H	Footing H	Volume, cu.ft	Footing -	rebar (lower)	Footing - rebar (upper)					
MAIN BUI	LDING								1	No/Size 1	Len (dec.ft)	No/Size 2	Len (dec.	ft]No/Size 1	Len (dec.f	t; No/Size 2	Len (dec.ft)
Α		5 MB-A	7.5000	5.5000	2.0000	1.2500	3.0000	1.3330	312.43	7 - #4	7.5000	9 - #4	5.5000	7 - #4	7.5000	9 - #4	5.5000
В		8 MB-B	7.5000	5.5000	2.0000	1.2500	3.0000	1.3330	499.89	7 - #4	7.5000	9 - #4	5.5000	7 - #4	7.5000	9 - #4	5.5000
С		0 MB-C	7.5000	5.5000	2.0000	1.2500	3.0000	1.3330	0.00	7 - #4	7.5000	9 - #4	5.5000	7 - #4	7.5000	9 - #4	5.5000
D		0 MB-D	7.5000	5.5000	2.0000	1.2500	3.0000	1.3333	0.00	7 - #4	7.5000	9 - #4	5.5000	7 - #4	7.5000	9 - #4	5.5000
E		1 MB-E	12.2500	8.7500	2.7500	1.7500	3.0000	1.3333	157.35	10 - #6	12.2500	13 - #5	8.7500	10 - #4	12.2500	13 - #4	8.7500
F		12 MB-F	12.2500	8.7500	2.7500	1.7500	3.0000	1.3333	1888.21	10 - #6	12.2500	13 - #5	8.7500	10 - #4	12.2500	13 - #4	8.7500
G		1 MB-G	12.2500	8.7500	2.7500	1.7500	3.0000	1.3333	157.35	10 - #6	12.2500	13 - #5	8.7500	10 - #4	12.2500	13 - #4	8.7500
Н		12 MB-H	12.2500	8.7500	2.7500	1.7500	3.0000	1.3333	1888.21	10 - #6	12.2500	13 - #5	8.7500	10 - #4	12.2500	13 - #4	8.7500
								Total:	4903.44								
BUILDING	32																
Α		0 B2-A	7.0000	5.0000	2.0000	1.1250	2.0000	1.2400	0.00								
В		0 B2-B	7.0000	5.0000	2.0000	1.1250	2.0000	1.2400	0.00								
С		13 B2-C	7.0000	5.0000	2.0000	1.1250	3.0000	1.3333	694.40	6 - #4	7.0000	8 - #4	5.0000	6 - #4	7.0000	8 - #4	5.0000
								Total:	694.40								
BUILDING	<del>3</del> 3																
Α		9 B3-A	6.0000	5.0000	2.0000	1.1250	3.0000	1.3333	420.74	6 - #4	6.0000	7 - #4	5.0000	6 - #4	6.0000	7 - #4	5.0000
В		0 B3-B	9.0000	5.0000	2.0000	1.1250	2.0000	1.2400	0.00								
С		0 B3-C	9.0000	5.0000	2.0000	1.1250	2.0000	1.2400	0.00								
D		0 B3-D	9.0000	5.0000	2.0000	1.1250	2.0000	1.2400	0.00								
FROST WALLS								Total:	420.74							_	
FW-A	_	750 B3-A	1.	5 -	0.75	5 -	3.0000	1.3333	3187.46	•							
1 2 3 4 5 6																	
								Total:	3608.20								