

1" CONSTRUCTION TOLERANCE ALL AROUND

P13A 1/2" = 1'-0" P13B 1/2" = 1'-0"

P14 1/2" = 1'-0"

MARK	VERTICAL REINF	PIER TIES	ELEV OF TOP OF PIER	ANCHOR BOLT	REMARKS
P1	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P2	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
Р3	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P4	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P5	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P5A	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P5B	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P5C	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P6	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P6A	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P7	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P8	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P9	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P10					NOT IN USE
P11	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P11A	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P12	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P13	(8) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P13A	(8) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P13B					NOT IN USE
P14	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-

PIER SCHEDULE

	fs = 3000 psf				
	f'c = 3000 psi				
	SIZE			REINFORCING	
MARK	L	S	D	LONG BARS	SHORT BARS
F5	5'-0"	5'-0"	1'-6"	6 #4	6 #4
F7	7'-0"	7'-0"	2'-0"	8 #5	8 #5
F8	8'-0"	8'-0"	1'-6"	9 #6	9 #6
F10	10'-0"	10'-0"	2'-0"	11 #5	11 #5
F11	11'-6"	11'-6"	2'-0"	13 #5	13 #5



Owner
4860 Highwood Circle
Middleton, Wisconsin 53562
Todd Goldbeck
todd@xcel.net
608-279-6960



General Contractor
Krause Custom Builders
N3897 Duck Creek Rd
Helenville, WI 53137
Toby Krause
tobykrause@gmail.com
920-285-6490

Civil
Lake Country Engineering
970 S. Silver Lake Street, Suite 105
Oconomowoc, WI 53066
Rob Davy robd@lce.biz
(262) 569-933



Landscape
Ground Affects Landscaping, Inc.
W1526 Froelich Rd.
Sullivan, WI 53178
Tom Ball
tom@groundaffectslandscaping.com
262.593.8400



Architect
OpeningDesign
312 W. Lakeside St
Madison, WI 53715"
Ryan Schultz
ryan@openingdesign.com
773-425-6456



Structural
ntrive
280 Shuman Blvd, Suite 270
Naperville, IL 60563
Steven Uecke
s.uecke@ntrive.com
630-480-4120x101



Metal Building Manufacturer
Foremost Buildings, Inc.
895 N Parkway Street
Jefferson WI 53549
Jim Horn
JimH@foremostbuildings.com
920-674-5028



HVAC
Lake Country Heating and Cooling
N6333 Hwy F
Oconomowoc, WI 53066
Jim Shuda
jim@lakecountryhvac.com
414-573-1047



Electrical
Jefferson Current Electric
1473 S. Industrica Ave
Jefferson, WI 53549
Ross Davis
j.current.electric@att.net
920-674-6444



Plumbing
Pelikan Plumbing
144 Main St
Sullivan, WI 53178
Mike Pelikan
pelikanplumbing@yahoo.com
262-593-2290

No.	Description	Date
	ISSUED FOR PERMIT	07.08.2015
	IFC - FOOTING AND FOUNDATION	07.29.2015
	REISSUED FOR REVISED REACTION	08.06.2015
	ADDED DIMENSIONS	08.10.2015

Xcel Sports Complex

SCHEDULES, BASE PLATE AND PIER DETAILS

Date

8/10/2015 3:34:22 PM

S-10[°]

Scale As indicated