

P14 1/2" = 1'-0"

1" CONSTRUCTION TOLERANCE ALL AROUND

P13B 1/2" = 1'-0"

P13A 1/2" = 1'-0"

MARK	VERTICAL REINF	PIER TIES	ELEV OF TOP OF PIER	ANCHOR BOLT	REMARKS
P1	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P2	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P3	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P4	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P5	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P5A	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P5B	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P5C	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P6	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P6A	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P7	(4) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P8	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P9	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P10					NOT IN USE
P11	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P11A	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P12	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P13	(8) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P13A	(8) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P13B					NOT IN USE
P14	(6) #6	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-

PIER SCHEDULE

	fs = 3000 psf				
	f'c = 3000 psi				
	SIZE			REINFORCING	
MARK	L	S	D	LONG BARS	SHORT BARS
F5	5'-0"	5'-0"	1'-6"	6 #4	6 #4
F7	7'-0"	7'-0"	2'-0"	8 #5	8 #5
F8	8'-0"	8'-0"	1'-6"	9 #6	9 #6
F10	10'-0"	10'-0"	2'-0"	11 #5	11 #5
F11	11'-6"	11'-6"	2'-0"	13 #5	13 #5



Owner
4860 Highwood Circle
Middleton, Wisconsin 53562
Todd Goldbeck
todd@xcel.net
608-279-6960





Civil
Lake Country Engineering
970 S. Silver Lake Street, Suite 105
Oconomowoc, WI 53066
Rob Davy robd@lce.biz
(262) 569-933



Landscape
Ground Affects Landscaping, Inc.
W1526 Froelich Rd.
Sullivan, WI 53178
Tom Ball
tom@groundaffectslandscaping.com
262.593.8400



OpeningDesign 312 W. Lakeside St Madison, WI 53715" Ryan Schultz ryan@openingdesign.com 773-425-6456



Structural
ntrive
280 Shuman Blvd, Suite 270
Naperville, IL 60563
Steven Uecke
s.uecke@ntrive.com
630-480-4120x101







HVAC
Lake Country Heating and Cooling
N6333 Hwy F
Oconomowoc, WI 53066
Jim Shuda
jim@lakecountryhvac.com
414-573-1047



Electrical
Jefferson Current Electric
1473 S. Industrica Ave
Jefferson, WI 53549
Ross Davis
j.current.electric@att.net
920-674-6444



Plumbing
Pelikan Plumbing
144 Main St
Sullivan, WI 53178
Mike Pelikan
pelikanplumbing@yahoo.com
262-593-2290

No.	Description	Date	
	ISSUED FOR PERMIT	07.08.2015	
	IFC - FOOTING AND FOUNDATION	07.29.2015	
	REISSUED FOR REVISED REACTION	08.06.2015	
	ADDED DIMENSIONS	08.10.2015	`
	EAST WALL MODIFICATIONS	08.18.2015	/

Xcel Sports Complex

SCHEDULES, BASE PLATE AND PIER DETAILS

IF THERE ARE ANY DIMENSIONAL DISCREPANCIES
BETWEEN THE STRUCTURAL FOUNDATION PLAN
AND THE PEMB ANCHOR BOLT PLAN NOTIFY
ENTIRE TEAM (GC, CONCRETE SUB, ARCHITECT,
STRUCTURAL ENGINEER, AND PEMB REP) BEFORE
FORMING AND POURING CONCRETE

Scale 8/18/2015 12:43:32 PM

Scale 8/18/2015 12:43:32 PM

As indicated