

PIER SCHEDULE						
MARK	VERTICAL REINF	REINF DETAIL	PIER TIES	ELEV OF TOP OF PIER	ANCHOR BOLT	REMARKS
P1	(4) #6	1/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P2	(6) #6	2/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P3	(8) #6	3/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P4	(6) #6	4/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P5	(6) #6	5/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P5A	(6) #6	6/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P5B	(6) #6	7/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P5C	(6) #6	8/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P6	(8) #6	9/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P6A	(8) #6	10/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P7	(8) #6	11/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P8	(10) #6	12/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P9	(10) #6	13/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P10	(12) #6	14/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P11	(10) #6	15/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P11A	(10) #6	16/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 5/8" Ø x 7-1/2" EMBED	-
P12	(12) #6	17/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P13	(16) #6	18/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P13A	(12) #6	19/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 1" Ø x 12" EMBED	-
P13B	(12) #6	20/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P14	(14) #6	21/S-101	(3) #3 @ 2" REST #3 @12"	99'-0"	(4) 3/4" Ø x 9" EMBED	-
P15	TBD	TBD	TBD	99'-0"	TBD	-

FOOTING SCHEDULE					f <sub>s</sub> = 3000 psi f <sub>c</sub> = 3000 psi	
MARK	SIZE			REINFORCING		
	L	S	D	LONG BARS	SHORT BARS	
F5	5'-0"	5'-0"	1'-6"	6 #4	6 #4	
F7	7'-0"	7'-0"	2'-0"	8 #5	8 #5	
F8	8'-0"	8'-0"	1'-6"	9 #6	9 #6	
F10	10'-0"	10'-0"	2'-0"	11 #5	11 #5	
F11	11'-6"	11'-6"	2'-0"	13 #5	13 #5	



**Owner**  
4860 Highwood Circle  
Middleton, Wisconsin 53562  
Todd Goldbeck  
todd@xcel.net  
608-279-6960



**General Contractor**  
Krause Custom Builders  
N3897 Duck Creek Rd  
Helenville, WI 53137  
Toby Krause  
tobykrause@gmail.com  
920-285-6490



**Civil**  
Lake Country Engineering  
970 S. Silver Lake Street, Suite 105  
Oconomowoc, WI 53066  
Rob Davy      robd@lce.biz  
(262) 569-933



**Landscape**  
Ground Affects Landscaping, Inc.  
W1526 Froelich Rd.  
Sullivan, WI 53178  
Tom Ball  
tom@groundaffectslandscaping.com  
262.593.8400



**Architect**  
OpeningDesign  
312 W. Lakeside St  
Madison, WI 53715\*  
Ryan Schultz  
ryan@openingdesign.com  
773-425-6456



**Structural**  
ntrive  
280 Shuman Blvd, Suite 27  
Naperville, IL 60563  
Steven Uecke  
s.uecke@ntrive.com  
630-480-4120x101



**Metal Building Manufacturers**  
Foremost Buildings, Inc.  
895 N Parkway Street  
Jefferson WI 53549  
Jim Horn  
JimH@foremostbuildings.com  
920-674-5028



**HVAC**  
Lake Country Heating and Cooling  
N6333 Hwy F  
Oconomowoc, WI 53066  
Jim Shuda  
jim@lakecountryhvac.com  
414-573-1047



**Electrical**  
Jefferson Current Electric  
1473 S. Industria Ave  
Jefferson, WI 53549  
Ross Davis  
j.current.electric@att.net  
920-674-6444



**Plumbing**  
Pelikan Plumbing  
144 Main St  
Sullivan, WI 53178  
Mike Pelikan  
pelikanplumbing@yahoo.com  
262-593-2290

[illegible]

Xcel  
Sports Complex

## SCHEDULES, BASE PLATE AND PIER DETAILS


Date 07/08/2015

S-101

Scale As indicated

7/29/2015 10:06:38 PM





 Pelikan Plumbing LLC

**Plumbing**  
Pelikan Plumbing  
44 Main St  
Sullivan, WI 53178  
Mike Pelikan  
pelikanplumbing@yahoo.com  
662-593-2290

[illegible]

Xcel  
Sports Complex

## FOUNDATION PLAN

Date 07/08/2015







# S-200

Scale  $1/8" = 1'-0"$









Xcel  
Sports Complex

Date	07/08/2015
S-300	
Scale	As indicated